

土石方数量汇总表

丹锡高速经棚至阿其乌拉段公路(JATJ-01)（经棚西互通）

起点桩号	终点桩号	长度(m)	挖方(m³)					填方(m³)								废方		计价土石方	总运量	备注		
			总体积					压实方	填土	填石	远运利用方		本桩利用方		借方		土方				石方	
				松土	普通土	硬土	软石		天然方	天然方	土方	石方	土方	石方	土方	石方	m³	m³	m³		(立方米公里)	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	
主线																						
K0+000 ~ K1+400		1400						595123	732001						732001						跨线桥桥台后特别夯实区土方已计入跨线桥防护工程材料数量表内，本表未计	
小计								595123	732001						732001							
B匝道																						
K0+136.940 ~ K0+442.684		305.744	175	175				8078	9936		9761		175		0							
C匝道																						
K0+000.000 ~ K0+514.060		514.06	32	32				18467	22715				32		22683							
D匝道																						
K0+191.933 ~ K0+721.040		529.107	44	44				144753	178046				44		178002							
E匝道																						
K0+059.098 ~ K0+308.753		249.655	505	505				80672	99227		14000		505		84722							
匝道小计			756	756				251970	309923		23761		756		285406							
被交道																						
K1+600 ~ K3+860		2260	55357	55357				16370	20135		6034		14101		0		11461				含超宽填筑土方300方，废方调于B匝道9761方，调于E匝道14000方。	
小计			55357	55357				16370	20135		6034		14101		0		11461					
路基超宽填筑土方								11700	14391						14391							
小计								11700	14391						14391							
									注													
									取土场位于K2+500左300m处，借方运距2.1Km，远运运距500m；弃土场位于K6+500左200m处，弃方运距6Km。													
合 计			56113	56113				875163	1076450		29795		14857		1031799		11461					