

## 路基每公里土石方数量表

丹锡高速经棚至阿其乌拉段公路(JATJ-05)

第 1 页 共 1 页 S3-19

起 讫 桩 号	长 度	挖 方 (m³)					填 方 (m³)										废 方 (m³)				计价土石方	备 注
		总体积	土 方		石 方		总数量				本桩利用		远运利用			借 方	土方					
	(m)		松土	硬土	软石	次坚石	压实方	松土	硬土	软石	松土	硬土	松土	硬土	软石	松土	松土	硬土	次坚石	(m³)		
K47+900~K48+000	100	312		312			1781	1945	218			218				1945		94		2257		
K48+000~K48+500	500	1544		1544			20790	24004	1390			880		510		24004		154		25548		
K48+500~K49+000	500						57134	70275								70275				70275		
K49+000~K50+925	361						50831	62522								62522				62522		
K50+925~K51+000	75						14058	17291								17291				17291		
K51+000~K52+000	1000	44		44			73970	90948	31			31				90948		13		90992		
K52+000~K53+000	1000						108998	134068								134068				134068		
K53+000~K54+000	1000						57191	70345								70345				70345		
K54+000~K55+000	1000						55929	68793								68793				68793		
K55+000~K56+000	1000						77946	95874								95874				95874		
K56+000~K57+000	1000						80304	98774								98774				98774		
K57+000~K58+000	1000						219606	270116								270116				270116		
K58+000~K59+000	1000						173533	213445								213445				213445		
K59+000~K60+000	1000	124988		12499	74993	37496	108987	21098	11249	74993		99		11150	74993	21098		1250	37496	146086		
K60+000~K61+000	1000	39138		38276	575	287	52504	22780	36362	575		126		36236	575	22780		1914	287	61917		
K61+000~K62+000	1000	41216		41216			34384		37479			283		37196		0		3738	0	41216		
K62+000~K63+200	1200																				达里湖互通	
K63+000~K64+000	800	1150		1150			32238	38486	1035			341		694		38486		115		39635		
K64+000~K64+422.560	423						45142	55525								55525				55525		
路基超宽填筑土方工程量							31646	38925								38925				38925		
JATJ-05标段小计	14959	208392		95041	75567	37784	1296974	1395213	87763	75567		1977		85786	75567	1395213		7277	37784	1603604		