

路基每公里土石方数量表

丹锡高速经棚至阿其乌拉段公路(JATJ-02)

第 1 页 共 1 页 S3-19

起 讫 桩 号	长 度	挖 方 (m³)					填 方 (m³)									废 方 (m³)				计价土石方	备 注
		总体积	土 方		石 方		总数量				本桩利用		远运利用			借 方	土方				
	(m)		松土	硬土	软石	次坚石	压实方	松土	硬土	软石	松土	硬土	松土	硬土	软石	松土	松土	硬土	次坚石	(m³)	
K1+400~K2+000	600						171025	210361								210361				210361	
K2+000~K3+000	1000						119875	147447						6966		140481				140481	K4调入 I 6966
K3+000~K4+000	1000	74674	74674				68667	84461			8769			75692			7467			74674	下公里调入 I 17254
K4+000~K3+814	101	30033	30033														3003			30033	
K3+814~K4+000	186	13600	13600				635	781			781						1360			13600	
K4+000~K5+000	1000	55653	55653				52323	64357			13935			50422			5565			55653	上公里调入 I 14269
K5+000~K6+000	1000	134754	134754				50443	62045			5194			56851			6738			134754	
K6+000~K7+000	1000	154905	154905				34803	42807			6279			36528			7745			154905	
K7+000~K8+000	1000	6105	6105				101575	124937			2723			122215			1221			6105	上公里调入 I 120053
K8+000~K9+000	1000						257944	317271						54617		262654				262654	K5~K6调入 I 50271 下公里调入 I 4346
K9+000~K10+000	1000	62844	62844				42450	52214			1281			50933			6284			62844	
K10+000~K11+000	1000	965	965				91226	112208			728					111480	237			112445	
K11+000~K12+000	1057	15037	15037				33132	40753			2520			11013		27219	1504			42257	
K12+000~K13+000	1000	1124		1124			60915	73783	1012			392		620		73783		112		74908	
K13+000~K14+000	1000	5308		5308			53576	60507	4778			2296		2481		60507		531		65815	
K14+000~K15+000	1000	26716	24653	2063			32673	37859	2063		989		21199	2063		15672	2465			42388	
K15+000~K16+000	1000	20292	16728	3564			23910	25387	3564		301		14754	3564		10332	1673			30624	
K16+000~K17+000	1000	14315	13142	1172			80840	98111	1172		192		11636	1172		86283	1314			100597	
K17+000~K17+500	500	7254	5846	1408			22033	25512	1408		232		5029	1408		20251	585			27505	
路基超宽填筑土方工程量							20076	24693								24693				24693	
JATJ-02标段小计	16444	623578	608938	14641			1318121	1605494	13997	0	43922	2688	517855	11309	0	1043717	47162	643		1667295	