

右幅病害处理工程数量表

工程名称： 内蒙古际通道连接线通辽至舍伯吐一级公路(K536+000～K542+000)改造处治工程

序号	桩号	位置	长度 (m)	车道及硬路肩宽 度(单幅) (m)	铣刨7cm面层 (m ²)	20cm水稳 基层就地 冷再生 (m ²)	挖除20cm 水稳基层 (m ²) (一 般路段)	20cm水稳底 基层就地冷 再生 (m ²) (一般路段)	回填20cm水 稳基层 (m ³) (一 般路段)	加铺5cmAC- 16沥青砼下 面层 (m ²)	加铺4cmAC-13 沥青砼上面层 (m ²)	粘层 (m ²)	透层 (m ²)	RPS抗车辙 剂(t)	热容型标 线 (m ²)	级配碎 石 (m ³)	桥面防 水层 (m ³)	备注
1	K536+000.000 ～K536+712.298	车道及硬路肩	712.3	11.25 ～15.00	10387.7	10387.7				10387.7	10387.7	10387.7	10387.7	5.09				互道路段
2	K536+712.298 ～K536+809.098	车道及硬路肩	96.8	15.00	1452.0					1452.0	1452.0	1452.0		0.71			1452.0	五家子互通跨线 桥段
3	K536+809.098 ～K537+300.000	车道及硬路肩	490.9	15.00 ～11.25	7159.0	7159.0				7159.0	7159.0	7159.0	7159.0	3.51				互道路段
4	K537+300.000 ～K537+517.600	车道及硬路肩	217.6	11.25	2448.0		2448.0	2448.0	2448.0	2448.0	2448.0	2448.0	2448.0	1.20				一般路段
5	K537+517.600 ～K537+550.400	车道及硬路肩	32.8	11.25	369.0					369.0	369.0	369.0		0.18			369.0	通道小桥段
6	K537+550.400 ～K538+000.000	车道及硬路肩	449.6	11.25	5058.0		5058.0	5058.0	5058.0	5058.0	5058.0	5058.0	5058.0	2.48				一般路段
7	K538+000.000 ～K539+293.100	车道及硬路肩	1293.1	11.25	14547.4					14547.4	14547.4	14547.4	14547.4	7.13				一般路段
8	K539+293.100 ～K539+941.900	车道及硬路肩	648.8	11.25										0.00				西辽河大桥段(已 维修改造)
9	K539+941.900 ～K540+459.600	车道及硬路肩	517.7	11.25	5824.1	5824.1				5824.1	5824.1	5824.1	5824.1	2.85				一般路段
10	K540+459.600 ～K540+524.400	车道及硬路肩	64.8	11.25	729.0					729.0	729.0	729.0		0.36			729.0	分离立交桥段
11	K540+524.400 ～K540+557.921	车道及硬路肩	33.5	11.25	377.1	377.1				377.1	377.1	377.1	377.1	0.18				互道路段
12	K540+557.921 ～K540+727.291	车道及硬路肩	169.4	11.25 ～16.23	2585.2	2585.2				2585.2	2585.2	2585.2	2585.2	1.27				互道路段
13	K540+727.291 ～K540+888.488	车道及硬路肩	161.2	11.25	1813.5	1813.5				1813.5	1813.5	1813.5	1813.5	0.89				互道路段
14	K540+888.488 ～K540+900.000	车道及硬路肩	11.5	16.23 ～14.33	195.4	195.4				195.4	195.4	195.4	195.4	0.10				互道路段
15	K540+900.000 ～K540+937.694	车道及硬路肩	37.7	14.33 ～14.30	599.5	599.5				599.5	599.5	599.5	599.5	0.29				互道路段
16	K540+937.694 ～K540+960.000	车道及硬路肩	22.3	14.30 ～15.00	363.1	363.1				363.1	363.1	363.1	363.1	0.18				互道路段
17	K540+960.000 ～K540+966.036	车道及硬路肩	6.0	15.00	90.5	90.5				90.5	90.5	90.5	90.5	0.04				互道路段
18	K540+966.036 ～K541+062.836	车道及硬路肩	96.8	15.00	1452.0					1452.0	1452.0	1452.0		0.71			1452.0	二号村互通桥段
19	K541+062.836 ～K541+114.498	车道及硬路肩	51.7	15.00	774.9	774.9				774.9	774.9	774.9	774.9	0.38				互道路段
20	K541+114.498 ～K541+140.000	车道及硬路肩	25.5	15.00 ～14.05	411.5	411.5				411.5	411.5	411.5	411.5	0.20				互道路段
21	K541+140.000 ～K541+161.649	车道及硬路肩	21.6	14.05 ～15.73	358.1	358.1				358.1	358.1	358.1	358.1	0.18				互道路段
22	K541+161.649 ～K541+295.060	车道及硬路肩	133.4	11.25	1500.9	1500.9				1500.9	1500.9	1500.9	1500.9	0.74				互道路段
23	K541+295.060 ～K541+461.338	车道及硬路肩	166.3	21.48 ～11.25	3023.0	3023.0				3023.0	3023.0	3023.0	3023.0	1.48				互道路段
24	K541+461.338 ～K541+467.100	车道及硬路肩	5.8	11.25	64.8	64.8				64.8	64.8	64.8	64.8	0.03				互道路段
25	K541+467.100 ～K541+492.900	车道及硬路肩	25.8	11.25	290.3					290.3	290.3	290.3		0.14			290.3	通道小桥段
26	K541+492.900 ～K542+000.000	车道及硬路肩	507.1	11.25	5704.9	5704.9				5704.9	5704.9	5704.9	5704.9	2.80				一般路段
27																		
28																		
29	合计		6000.0		67578.9	41233.3	7506.0	7506.0	7506.0	67578.9	67578.9	67578.9	63286.7	33.1	6708.0	642.5	4292.3	

编制：李俊广

复核： 张振伟

左幅病害处理工程数量表

工程名称： 内蒙古际通道连接线通辽至舍伯吐一级公路(K536+000～K542+000)改造处治工程

序号	桩号	位置	长度 (m)	车道及硬路肩宽度(双幅) (m)	铣刨7cm面层 (m ²)	20cm水稳基层就地冷再生 (m ²)	挖除20cm水稳基层 (m ²) (一般路段)	20cm水稳底基层就地冷再生 (m ²) (一般路段)	回填20cm水稳基层 (m ²) (一般路段)	加铺5cmAC-16沥青砼下面层 (m ²)	加铺4cmAC-13沥青砼上面层 (m ²)	粘层 (m ²)	透层 (m ²)	RPS抗车辙剂(t)	热容型标线 (m ²)	级配碎石 (m ³)	桥面防水层 (m ²)	备注
1	K536+000.000 ～K536+712.298	车道及硬路肩	712.3	11.25 ～15.00	10387.7	10387.7				10387.7	10387.7	10387.7	10387.7	5.09				互通路段
2	K536+712.298 ～K536+809.098	车道及硬路肩	96.8	15.00	1452.0					1452.0	1452.0	1452.0		0.71			1452.0	五家子互通跨线桥段
3	K536+809.098 ～K537+300.000	车道及硬路肩	490.9	15.00 ～11.25	7159.0	7159.0				7159.0	7159.0	7159.0	7159.0	3.51				互通路段
4	K537+300.000 ～K537+517.600	车道及硬路肩	217.6	11.25	2448.0	2448.0				2448.0	2448.0	2448.0	2448.0	1.20				一般路段
5	K537+517.600 ～K537+550.400	车道及硬路肩	32.8	11.25	369.0					369.0	369.0	369.0		0.18			369.0	通道小桥段
6	K537+550.400 ～K539+293.100	车道及硬路肩	1742.7	11.25	19605.4	19605.4				19605.4	19605.4	19605.4	19605.4	9.61				一般路段
7	K539+293.100 ～K539+941.900	车道及硬路肩	648.8	11.25										0.00				西辽河大桥段(已维修改造)
8	K539+941.900 ～K540+459.600	车道及硬路肩	517.7	11.25	5824.1	5824.1				5824.1	5824.1	5824.1	5824.1	2.85				一般路段
9	K540+459.600 ～K540+524.400	车道及硬路肩	64.8	11.25	729.0					729.0	729.0	729.0		0.36			729.0	分离立交桥段
10	K540+524.400 ～K540+557.921	车道及硬路肩	33.5	11.25	377.1	377.1				377.1	377.1	377.1	377.1	0.18				互通路段
11	K540+557.921 ～K540+727.291	车道及硬路肩	169.4	11.25 ～15.73	2538.2	2538.2				2538.2	2538.2	2538.2	2538.2	1.24				互通路段
12	K540+727.291 ～K540+888.488	车道及硬路肩	161.2	11.25	1813.5	1813.5				1813.5	1813.5	1813.5	1813.5	0.89				互通路段
13	K540+888.488 ～K540+900.000	车道及硬路肩	11.5	15.73 ～14.33	192.2	192.2				192.2	192.2	192.2	192.2	0.09				互通路段
14	K540+900.000 ～K540+937.694	车道及硬路肩	37.7	14.33 ～16.30	641.4	641.4				641.4	641.4	641.4	641.4	0.31				互通路段
15	K540+937.694 ～K540+960.000	车道及硬路肩	22.3	16.30 ～15.00	387.9	387.9				387.9	387.9	387.9	387.9	0.19				互通路段
16	K540+960.000 ～K540+966.036	车道及硬路肩	6.0	15.00	90.5	90.5				90.5	90.5	90.5	90.5	0.04				互通路段
17	K540+966.036 ～K541+062.836	车道及硬路肩	96.8	15.00	1452.0					1452.0	1452.0	1452.0		0.71			1452.0	二号村互通桥段
18	K541+062.836 ～K541+114.498	车道及硬路肩	51.7	15.00	774.9	774.9				774.9	774.9	774.9	774.9	0.38				互通路段
19	K541+114.498 ～K541+140.000	车道及硬路肩	25.5	13.93 ～14.05	396.3	396.3				396.3	396.3	396.3	396.3	0.19				互通路段
20	K541+140.000 ～K541+161.649	车道及硬路肩	21.6	14.05 ～15.73	358.1	358.1				358.1	358.1	358.1	358.1	0.18				互通路段
21	K541+161.649 ～K541+295.060	车道及硬路肩	133.4	11.25	1500.9	1500.9				1500.9	1500.9	1500.9	1500.9	0.74				互通路段
22	K541+295.060 ～K541+461.338	车道及硬路肩	166.3	21.48 ～11.25	3023.0	3023.0				3023.0	3023.0	3023.0	3023.0	1.48				互通路段
23	K541+461.338 ～K541+467.100	车道及硬路肩	5.8	11.25	64.8	64.8				64.8	64.8	64.8	64.8	0.03				互通路段
24	K541+467.100 ～K541+492.900	车道及硬路肩	25.8	11.25	290.3					290.3	290.3	290.3		0.14			290.3	通道小桥段
25	K541+492.900 ～K542+000.000	车道及硬路肩	507.1	11.25	5704.9	5704.9				5704.9	5704.9	5704.9	5704.9	2.80				一般路段
26																		
27																		
28	合计		6000.0		67580.1	63287.9	0.0	0.0	0.0	67580.1	67580.1	67580.1	63287.9	33.1	6708.0	642.6	4292.3	

编制： 李俊广

复核： 张振伟